

SNAPNRACK RL UNIVERSAL SOLAR MOUNTING SOLUTION INSTALLED ON A COMPOSITION SHINGLE ROOF



MINIMIZE ROOF ATTACHMENTS ON STAGGERED ARRAYS BY USING A SNAPNRACK RL UNIVERSAL LINK TO SUPPORT THE MODULE CANTILEVER INSTEAD OF A ROOF MOUNT

FOR LINK DETAILS REFER TO "SNR-DC-00364 RL UNIVERSAL, COMPONENT DETAIL, LINK"

REQUIREMENTS FOR LINKS ON STAGGERED ARRAYS:

- 1) WHEN LINKING PANELS IN THE SAME ROW, A LINK SHALL OCCUR WITHIN 1" TO 6" FROM THE NEAREST ADJACENT MODULE PANEL EDGE
- 2) ROOF ATTACHMENT SPACING(S) SHALL NOT BE EXCEEDED WITH THE USE OF LINK(S)
- 3) IN ANY CASE, A MAX OF (2) ROOF ATTACHMENTS PER MODULE MAY BE REPLACED WITH UTILIZATION OF LINK(S)

REVISION:			
NO.	DATE	DESCRIPTION	BY
1	5/28/2019	NEW DETAIL	DR



Sunrun South LLC  
 595 MARKET STREET, 29TH FLOOR • SAN FRANCISCO, CA 94105 USA  
 PHONE (415) 580-6900 • FAX (415) 580-6902  
THE INFORMATION IN THIS DRAWING IS CONFIDENTIAL AND PROPRIETARY. ANY REPRODUCTION, DISCLOSURE, OR USE THEREOF IS PROHIBITED WITHOUT THE WRITTEN CONSENT OF SUNRUN SOUTH LLC.

DESIGNER: B.PETERSON  
 DRAFTER: D.RYAN  
 APPROVED BY: B.PETERSON

SCALE: NTS  
 DATE: 5/28/2019

DRAWING NUMBER:  
SNR-DC-00368

DESCRIPTION: RL UNIVERSAL, SYSTEM OVERVIEW, STAGGERED ARRAYS

REV: 1